

**ESTIMATED QUANTITIES - MAW (LONG ALEC CREEK) FISH PASSAGE**

**40' Steel Bridge**

Item No.	Item Description	WDOT Division	Approx. Quantity	Units	Unit Price	Bid Amount
1	Mobilization, Utilities and Demobilization	1-09	1	LS	N/A	\$
2	Diversion, Erosion and Water Pollution Control	8-01	1	LS	N/A	\$
3	Install and Remove Temporary Access Road		1	LS	N/A	\$
4	Culvert Removal & Disposal	2-02	1	EA	\$	\$
5	Excavation and Disposal	2-09	560	CY	\$	\$
6	Gravel Base Under Footings	9-03	27	CY	\$	\$
7	Install T-Footing Bridge Abutments	6-02	1	LS	N/A	\$
8	Structural Fill & Compaction	2-09	290	CY	\$	\$
9	Grade Control (Rock Large Rock 18"-36")	9-13	12	EA	\$	\$
10	Streambed Material	9-03	40	CY	\$	\$
11	Install 40' Steel Bridge, End Walls, guardrail assembly, etc.	6-02	1	LS	N/A	\$
12	Loose Riprap (8" to 24")	8-15 9-13	60	CY	\$	\$
13	Road Riprap (3" to 8")	8-15 9-13	10	CY	\$	\$
14	Crushed Surfacing (Base & Top)	9-03	30	CY	\$	\$
15	Restoration	8-01	1	LS	N/A	\$

- a) Quantities are approx. and based on dimensions from CAD Drawings  
 b) LS.= Lump Sum, C.Y. = Cubic Yard

<b>BASE BID</b>	\$
Sales Tax (8.0%)	\$
<b>Total Bid (Base Bid + Tax)</b>	\$

Contractor: \_\_\_\_\_

Date: \_\_\_\_\_